

Workboat LIL P



SPECIFICATIONS

Workboat	Lil P
Length	38ft
Breadth	10ft
Depth	3ft
Draft	2ft

Description:

Vessel built of all welded Aluminum construction, completed in May 2009.

Vessel has a flush deck, superstructure with aluminum watertight doors and rubber gasket mounted weather tight windows.

20x10 cargo deck fwd

Vessel carries 750 gallons of portable water.

Fresh water pump

Raw water pump

Arrangement:

Cabin has bench seats to carry 10 passengers

The cabin is equipped with :

(1)Furuno VX2 Radar, (1) Furuno GPS chart plotter, (1) Furuno Dept Reader, (2) Standard VHF, (1) Spot light remote control (1) 15.5 BTU Air Conditioners

Engines:

(2) 250 Yamaha 4 stroke engines

carries 350 gallons of gasoline and 100 gallons of Diesel

(1) 6 KW Keel cooled Kabota Diesel Generator

